NEW FADOR		Conforms to Reg. (EU) 878/2020			Board Code S-P4/2-2 Board Date 05/2010 Board Rev. 1	
Document n°	Revision date	Rev. N°	Edited by	Approved by	Filed by	Page
66/09	27.07.2022	8	RLAB	DG	RLAB	1 di 13

SECTION 1. Identification of the substance/mixture and of the company/undertaking

F_162
CANDEGGINA GEL AMACASA
WC CANDEGGINA GEL AMACASA
RS63-20GJ-300J-AEKU

1.2. Relevant identified uses of th	ne substance or mixture and uses advised	l against	
dentified Uses	Industrial	Professional	

1.2. Relevant identified uses of the substance or mixture and uses advised against					
Identified Uses	Industrial	Professional	Consumer		
Toilet cleaner	-	~	~		
hard surface cleaner	-	~	~		
Whitener and bleach	-	~	✓		
Uses Advised Against					

Do not use for uses other than those indicated

1.3. Details of the supplier of the safety data sheet Name Full address District and Country	NEW FADOR S.r.I. via Mario Calderara, 31 25018 Montichiari (BS) Italia Tel. +39 030961 243 www.newfador.it
e-mail address of the competent person responsible for the Safety Data Sheet	info@newfador.it
1.4. Emergency telephone number For urgent inquiries refer to	NEW FADOR S.r.I.
	+39 030961 243
	(08.30 - 17.30)

SECTION 2. Hazards identification

2.1. Classification of the substance or mixture

The product is classified as hazardous pursuant to the provisions set forth in (EC) Regulation 1272/2008 (CLP) (and subsequent amendments and supplements). The product thus requires a safety datasheet that complies with the provisions of (EU) Regulation 2020/878. Any additional information concerning the risks for health and/or the environment are given in sections 11 and 12 of this sheet.

Hazard classification and indication:		
Substance or mixture corrosive to metals, category 1	H290	May be corrosive to metals.
Skin corrosion, category 1A	H314	Causes severe skin burns and eye damage.
Serious eye damage, category 1	H318	Causes serious eye damage.
Hazardous to the aquatic environment, chronic toxicity,	H412	Harmful to aquatic life with long lasting effects.
category 3		

2.2. Label elements

Hazard labelling pursuant to EC Regulation 1272/2008 (CLP) and subsequent amendments and supplements.

Hazard pictograms:



Signal words:

NEW FADOR		Material Safety Data Sheet Conforms to Reg. (EU) 878/2020				Board Code S-P4/2-2 Board Date 05/2010 Board Rev. 1
Document n°	Revision date	Rev. N°	Edited by	Approved by	Filed by	Page
66/09	27.07.2022	8	RLAB	DG	RLAB	2 di 13

Hazard statements:

H290 H314 H412 EUH206	May be corrosive to metals. Causes severe skin burns and eye damage. Harmful to aquatic life with long lasting effects. Warning! Do not use together with other products. May release dangerous gases (chlorine).
Precautionary statements:	
P101	If medical advice is needed, have product container or label at hand.
P102	Keep out of reach of children.
P260	Do not breathe dust / fume / gas / mist / vapours / spray.
P280	Wear protective gloves/ protective clothing / eye protection / face protection.

P280	Wear protective gloves/ protective clothing / eye protection / face protection.
P301+P330+P331	IF SWALLOWED: Rinse mouth. Do NOT induce vomiting.
P303+P361+P353	IF ON SKIN (or hair): Take off immediately all contaminated clothing. Rinse skin with water [or shower].
P305+P351+P338	IF IN EYES: Rinse cautiously with water for several minutes. Remove contact lenses, if present and easy to do. Continue
	rinsing.
P501	Dispose of contents/container in accordance to current regulation.
Contains:	SODIUM HYDROXIDE
	SODIUM HYPOCHLORITE, SOLUTION 2,2% CI ACTIVE

Ingredients according to Regulation (EC) No. 648/2004

Less than 5% anionic surfactants, non-ionic surfactants, chlorine-based bleaching agents, soap

perfumes

2.3. Other hazards

On the basis of available data, the product does not contain any PBT or vPvB in percentage \geq than 0,1%.

The product does not contain substances with endocrine disrupting properties in concentration $\ge 0.1\%$.

SECTION 3. Composition/information on ingredients

3.1. Substances

Information not relevant

3.2. Mixtures

Contains:

Identification	x = Conc. %	Classification (EC) 1272/2008 (CLP)
SODIUM HYPOCHLORITE,		
SOLUTION 2,2% CI ACTIVE		
CAS 7681-52-9	2 ≤ x < 2,5	Met. Corr. 1 H290,
		Skin Corr. 1B H314,
		Eye Dam. 1 H318,
		Aquatic Acute 1 H400 M=10,
		Aquatic Chronic 1 H410 M=1,
		EUH031, Classification note consultants Annow V() to the CLD Deputation, D
EC 231-668-3		Classification note according to Annex VI to the CLP Regulation: B
INDEX 017-011-00-1		
REACH Reg. 01-2119488154-34		
FATTY ACIDS, OLIVE-OIL,		
POTASSIUM SALTS		
CAS 68154-77-8	1 ≤ x < 1,5	Eye Irrit. 2 H319,
		Skin Irrit. 2 H315,
FO. 000 001 0		STOT SE 3 H335
EC 268-921-2		

INDEX -N,N-dimethyltetradecylamine N-

NEW FADOR			afety Da to Reg. (EU) 8	ata Shee	et	Board Code S-P4/2-2 Board Date 05/2010 Board Rev. 1
Document n°	Revision date	Rev. N°	Edited by	Approved by	Filed by	Page
66/09	27.07.2022	8	RLAB	DG	RLAB	3 di 13

oxide		
CAS 3332-27-2	1 ≤ x < 1,5	Acute Tox. 4 H302, Eye Dam. 1 H318, Skin Irrit. 2 H315, Aquatic Acute 1 H400 M=1, Aquatic Chronic 2 H411
EC 222-059-3		LD50 Oral: >1495
INDEX -		
REACH Reg. 01-2119949262-37		
SODIUM HYDROXIDE		
CAS 1310-73-2	0,6 ≤ x < 0,7	Met. Corr. 1 H290, Skin Corr. 1A H314, Eve Dam. 1 H318
EC 215-185-5		Skin Corr. 1B H314: ≥ 2%, Skin Irrit. 2 H315: ≥ 0,5%, Eye Dam. 1 H318: ≥ 2%, Eye Irrit. 2 H319: ≥ 0,5%
INDEX 011-002-00-6		··, , · · · · · · · · · · · · · · · · · · ·
REACH Reg 01-2119457892-27		

REACH Reg. 01-2119457892-27

The full wording of hazard (H) phrases is given in section 16 of the sheet.

SECTION 4. First aid measures

4.1. Description of first aid measures

EYES: Remove contact lenses, if present. Wash immediately with plenty of water for at least 30-60 minutes, opening the eyelids fully. Get medical advice/attention.

SKIN: Remove contaminated clothing. Rinse skin with a shower immediately. Get medical advice/attention.

INGESTION: Have the subject drink as much water as possible. Get medical advice/attention. Do not induce vomiting unless explicitly authorised by a doctor.

INHALATION: Get medical advice/attention immediately. Remove victim to fresh air, away from the accident scene. If the subject stops breathing, administer artificial respiration. Take suitable precautions for rescue workers.

4.2. Most important symptoms and effects, both acute and delayed

Specific information on symptoms and effects caused by the product are unknown.

4.3. Indication of any immediate medical attention and special treatment needed

Information not available

SECTION 5. Firefighting measures

5.1. Extinguishing media

SUITABLE EXTINGUISHING EQUIPMENT The extinguishing equipment should be of the conventional kind: carbon dioxide, foam, powder and water spray. UNSUITABLE EXTINGUISHING EQUIPMENT None in particular.

5.2. Special hazards arising from the substance or mixture

HAZARDS CAUSED BY EXPOSURE IN THE EVENT OF FIRE Do not breathe combustion products.

5.3. Advice for firefighters

GENERAL INFORMATION

Use jets of water to cool the containers to prevent product decomposition and the development of substances potentially hazardous for health. Always wear full fire prevention gear. Collect extinguishing water to prevent it from draining into the sewer system. Dispose of contaminated water used for extinction and the remains of the fire according to applicable regulations.

SPECIAL PROTECTIVE EQUIPMENT FOR FIRE-FIGHTERS

Normal firefighting clothing i.e. fire kit (BS EN 469), gloves (BS EN 659) and boots (HO specification A29 and A30) in combination with selfcontained open circuit positive pressure compressed air breathing apparatus (BS EN 137).



Material Safety Data Sheet

Conforms to Reg. (EU) 878/2020 Edited by

Approved by

	Board Rev. 1
Filed by	Page
RLAB	4 di 13

27.07.2022 8 RLAB DG RLAE

Rev. N°

SECTION 6. Accidental release measures

6.1. Personal precautions, protective equipment and emergency procedures

Revision date

Block the leakage if there is no hazard.

Wear suitable protective equipment (including personal protective equipment referred to under Section 8 of the safety data sheet) to prevent any contamination of skin, eyes and personal clothing. These indications apply for both processing staff and those involved in emergency procedures.

6.2. Environmental precautions

The product must not penetrate into the sewer system or come into contact with surface water or ground water.

6.3. Methods and material for containment and cleaning up

Collect the leaked product into a suitable container. Evaluate the compatibility of the container to be used, by checking section 10. Absorb the remainder with inert absorbent material.

Make sure the leakage site is well aired. Contaminated material should be disposed of in compliance with the provisions set forth in point 13.

6.4. Reference to other sections

Any information on personal protection and disposal is given in sections 8 and 13.

SECTION 7. Handling and storage

7.1. Precautions for safe handling

Before handling the product, consult all the other sections of this material safety data sheet. Avoid leakage of the product into the environment. Do not eat, drink or smoke during use. Remove any contaminated clothes and personal protective equipment before entering places in which people eat.

7.2. Conditions for safe storage, including any incompatibilities

Store only in the original container. Store the containers sealed, in a well-ventilated place, away from direct sunlight. Keep containers away from any incompatible materials, see section 10 for details.

7.3. Specific end use(s)


Information not available

SECTION 8. Exposure controls/personal protection

8.1. Control parameters

Regulatory References:

BGR	България	НАРЕДБА № 13 ОТ 30 ДЕКЕМВРИ 2003 Г. ЗА ЗАЩИТА НА РАБОТЕЩИТЕ ОТ РИСКОВЕ, СВЪРЗАНИ С ЕКСПОЗИЦИЯ НА ХИМИЧНИ АГЕНТИ ПРИ РАБОТА (изм. ДВ. бр.5 от 17 Януари 2020г.)
CZE	Česká Republika	Nařízení vlády č. 41/2020 Sb. Nařízení vlády, kterým se mění nařízení vlády č. 361/2007 Sb., kterým se stanoví podmínky ochrany zdraví při práci, ve znění pozdějších předpisů
DNK	Danmark	Bekendtgørelse om grænseværdier for stoffer og materialer - BEK nr 1458 af 13/12/2019
ESP	España	Límites de exposición profesional para agentes químicos en España 2021
FRA	France	Valeurs limites d'exposition professionnelle aux agents chimiques en France. ED 984 - INRS
GRC	Ελλάδα	Π.Δ. 26/2020 (ΦΕΚ 50/Α` 6.3.2020) Εναρμόνιση της ελληνικής νομοθεσίας προς τις διατάξεις των οδηγιών 2017/2398/ΕΕ, 2019/130/ΕΕ και 2019/983/ΕΕ «για την τροποποίηση της οδηγίας 2004/37/ΕΚ ``σχετικά με την προστασία των εργαζομένων από τους κινδύνους που συνδέονται με την έκθεση σε καρκινογόνους ή μεταλλαξιγόνους παράγοντες κατά την εργασία``»
HUN	Magyarország	Az innovációért és technológiáért felelős miniszter 5/2020. (II. 6.) ITM rendelete a kémiai kóroki tényezők hatásának kitett munkavállalók egészségének és biztonságának védelméről
HRV	Hrvatska	Pravilnik o izmjenama i dopunama Pravilnika o zaštiti radnika od izloženosti opasnimkemikalijama na radu, graničnim vrijednostima izloženosti i biološkim graničnim vrijednostima (NN 1/2021)
POL	Polska	Rozporządzenie ministra rozwoju, pracy i technologii z dnia 18 lutego 2021 r. Zmieniające rozporządzenie w sprawie najwyższych dopuszczalnych stężeń i natężeń czynników szkodliwych dla zdrowia w środowisku pracy
SVK	Slovensko	NARIADENIE VLÁDY Slovenskej republiky z 12. augusta 2020, ktorým sa mení a dopĺňa nariadenie vlády Slovenskej republiky č. 356/2006 Z. z. o ochrane zdravia zamestnancov pred rizikami súvisiacimi s expozíciou karcinogénnym a mutagénnym faktorom pri práci v znení neskorších predpisov



United Kingdom
TLV-ACGIH

GBR

EH40/2005 Workplace exposure limits (Fourth Edition 2020) ACGIH 2021

Predicted no-effect concentration	E, SOLUTION 2,2 on - PNEC							
Normal value in fresh water				0,00021	mç	g/I		
Normal value in marine water				0,000042	mg	g/I		
Normal value for water, intermit	ttent release			0,00026	mg	g/I		
Normal value of STP microorga	anisms			4,69	mg	g/I		
Normal value for the food chain	ו (secondary poison	ing)		11,1	mg	g/kg		
Health - Derived no-effect		MEL						
	Effects on consumers				Effects on workers			
Route of exposure	Acute local	Acute systemic	Chronic local	Chronic	Acute local	Acute	Chronic local	Chronic
Oral				systemic 0,26 mg/kg/d		systemic		systemic
Inhalation	3,1 mg/m3	3,1 mg/m3	1,55 mg/m3	1,55 mg/m3	3,1 mg/m3	3,1 mg/m3	1,55 mg/m3	1,55 mg/m
	e,	e,ge	.,	.,	-,·g	-, · · · · g. · · · -	.,	.,
N,N-dimethyltetradecylan	nine N-oxide							
Predicted no-effect concentration	on - PNEC							
Normal value in fresh water				0,034	mg	·		
Normal value in marine water				0,003	mg	·		
Normal value for fresh water se				5,24	-	g/kg		
Normal value for marine water				0,524	mg	g/kg		
Normal value of STP microorga				24	mg	g/I		
Normal value for the food chain		ing)		11,1	mg	g/kg		
Normal value for the terrestrial	compartment			1,02	mg	g/kg		
Health - Derived no-effect	t level - DNEL / D Effects on consumers	DMEL			Effects on workers			
Route of exposure	Acute local	Acute systemic	Chronic local	Chronic systemic	Acute local	Acute systemic	Chronic local	Chronic systemic
Oral				0,44 mg/kg bw/d				
Inhalation				1,53 mg/m3				6,2 mg/m3
Skin				5,5 mg/kg bw/d				11 mg/kg bw/d
SODIUM HYDROXIDE Threshold Limit Value								
Type	Country	TWA/8h		STEL/15min		Remarks	/	
						Observat	ions	
TLV	RCP	mg/m3	ppm	mg/m3	ppm			
TLV	BGR	2		2				
TLV	CZE	1		2				
TLV	DNK	2						
VLA	ESP	2						
VLEP	FRA	2		0				
TLV	GRC	2		2				
AK	HUN	2		2				
GVI/KGVI	HRV			2				
NDS/NDSCh	POL	0,5		1				
NPEL	SVK	2						
	GBR			2				
WEL				2 (C)				
WEL TLV-ACGIH				2(0)				
WEL TLV-ACGIH Health - Derived no-effect	t level - DNEL / C Effects on consumers	DMEL		2 (0)	Effects on workers			

NEW FADOR	Material Safety Data Sheet Conforms to Reg. (EU) 878/2020					Board Code S-P4/2-2 Board Date 05/2010 Board Rev. 1
Document n°	Revision date	Rev. N°	Edited by	Approved by	Filed by	Page
66/09	27.07.2022	8	RLAB	DG	RLAB	6 di 13

VND = hazard identified but no DNEL/PNEC available ; NEA = no exposure expected ; NPI = no hazard identified ; LOW = low hazard ; MED = medium hazard ; HIGH = high hazard.

8.2. Exposure controls

As the use of adequate technical equipment must always take priority over personal protective equipment, make sure that the workplace is well aired through effective local aspiration.

When choosing personal protective equipment, ask your chemical substance supplier for advice.

Personal protective equipment must be CE marked, showing that it complies with applicable standards.

Provide an emergency shower with face and eye wash station.

HAND PROTECTION

Protect hands with category III work gloves (see standard EN 374).

The following should be considered when choosing work glove material: compatibility, degradation, failure time and permeability.

The work gloves' resistance to chemical agents should be checked before use, as it can be unpredictable. The gloves' wear time depends on the duration and type of use.

SKIN PROTECTION

Wear category III professional long-sleeved overalls and safety footwear (see Regulation 2016/425 and standard EN ISO 20344). Wash body with soap and water after removing protective clothing.

EYE PROTECTION

Wear a hood visor or protective visor combined with airtight goggles (see standard EN 166).

RESPIRATORY PROTECTION

If the threshold value (e.g. TLV-TWA) is exceeded for the substance or one of the substances present in the product, use a mask with a type A filter whose class (1, 2 or 3) must be chosen according to the limit of use concentration. (see standard EN 14387). In the presence of gases or vapours of various kinds and/or gases or vapours containing particulate (aerosol sprays, fumes, mists, etc.) combined filters are required.

Respiratory protection devices must be used if the technical measures adopted are not suitable for restricting the worker's exposure to the threshold values considered. The protection provided by masks is in any case limited.

If the substance considered is odourless or its olfactory threshold is higher than the corresponding TLV-TWA and in the case of an emergency, wear open-circuit compressed air breathing apparatus (in compliance with standard EN 137) or external air-intake breathing apparatus (in compliance with standard EN 138). For a correct choice of respiratory protection device, see standard EN 529.

ENVIRONMENTAL EXPOSURE CONTROLS

The emissions generated by manufacturing processes, including those generated by ventilation equipment, should be checked to ensure compliance with environmental standards.

Product residues must not be indiscriminately disposed of with waste water or by dumping in waterways.

SECTION 9. Physical and chemical properties

9.1. Information on basic physical and chemical properties

Properties Appearance	Value liquid	Information
Colour	green	
Odour	characteristic	
Melting point / freezing point	not available	
Initial boiling point	not available	
Flammability	not available	
Lower explosive limit	not available	
Upper explosive limit	not available	
Flash point	not available	
Auto-ignition temperature	not available	
Decomposition temperature	not available	
рН	> 11.5	
Kinematic viscosity	not available	
Dynamic viscosity	400 ± 100 mPa*s (25 °C; rotore 2; velocità 30)	
Solubility	not available	
Partition coefficient: n-octanol/water	not available	
Vapour pressure	not available	
Density and/or relative density	1,025 g/cm3	
Relative vapour density	not available	

NEW FADOR	Material Safety Data Sheet Conforms to Reg. (EU) 878/2020					Board Code S-P4/2- Board Date 05/2010 Board Rev. 1
Document n°	Revision date	Rev. N°	Edited by	Approved by	Filed by	Page
66/09	27.07.2022	8	RLAB	DG	RLAB	7 di 13

Particle characteristics

not applicable

9.2. Other information

9.2.1. Information with regard to physical hazard classes

Information not available

9.2.2. Other safety characteristics

Explosive properties

Oxidising properties

not classified as explosive, contains no explosive substances according to CLP Art. (14 (2)) the product is not an oxidizing substance

SECTION 10. Stability and reactivity

10.1. Reactivity

There are no particular risks of reaction with other substances in normal conditions of use.

10.2. Chemical stability

The product is stable in normal conditions of use and storage.

10.3. Possibility of hazardous reactions

No hazardous reactions are foreseeable in normal conditions of use and storage.

10.4. Conditions to avoid

None in particular. However the usual precautions used for chemical products should be respected.

SODIUM HYDROXIDE Avoid exposure to: air, moisture, sources of heat.

10.5. Incompatible materials

SODIUM HYDROXIDE Incompatible with: strong acids, ammonia, zinc, lead, aluminium, water, flammable liquids.

10.6. Hazardous decomposition products

Information not available

SECTION 11. Toxicological information

In the absence of experimental data for the product itself, health hazards are evaluated according to the properties of the substances it contains, using the criteria specified in the applicable regulation for classification. It is therefore necessary to take into account the concentration of the individual hazardous substances indicated in section 3, to evaluate the toxicological effects of exposure to the product.

11.1. Information on hazard classes as defined in Regulation (EC) No 1272/2008

Metabolism, toxicokinetics, mechanism of action and other information Information not available Information on likely routes of exposure Information not available Delayed and immediate effects as well as chronic effects from short and long-term exposure Information not available Interactive effects Information not available



Revision date

27.07.2022

Material Safety Data Sheet

Conforms to Reg. (EU) 878/2020 Edited by

RLAB

Approved by

DG

Rev. N°

8

RLAB	8 di 13
Filed by	Page
	Board Rev. 1
	Board Date 05/2010
	Board Code S-P4/2-2

ACUTE TOXICITY	
ATE (Inhalation) of the mixture:	Not classified (no significant component)
ATE (Oral) of the mixture:	>2000 mg/kg
ATE (Dermal) of the mixture:	Not classified (no significant component)
SODIUM HYPOCHLORITE, SOLUTION 2,2% CI ACTIVE	
LD50 (Dermal):	> 10000 mg/kg rabbit
LD50 (Oral):	1100 mg/kg rat
LC50 (Inhalation vapours):	> 10,5 mg/l/1h rat
N,N-dimethyltetradecylamine N-oxide	
LD50 (Dermal):	> 2000 mg/kg
LD50 (Oral):	> 1495 mg/kg
ED50 (Oral).	> 1495 mg/kg
SODIUM HYDROXIDE	
LD50 (Oral):	325 mg/kg bw
Ebbo (ora).	S23 mg/kg Sw
SKIN CORROSION / IRRITATION	
Corrosive for the skin	
Classification according to the experimental pH value	
SERIOUS EYE DAMAGE / IRRITATION	
Causes serious eye damage	
RESPIRATORY OR SKIN SENSITISATION	
Does not meet the classification criteria for this hazard class	
Respiratory sensitization	
Information not available	
Skin sensitization	
Information not available	
GERM CELL MUTAGENICITY	
Does not meet the classification criteria for this hazard class	
CARCINOGENICITY	
Does not meet the classification criteria for this hazard class	
<u>REPRODUCTIVE TOXICITY</u> Does not meet the classification criteria for this hazard class	
Adverse effects on sexual function and fertility	
Information not available	
Adverse effects on development of the offspring Information not available	
Effects on or via lactation Information not available	
<u>STOT - SINGLE EXPOSURE</u> Does not meet the classification criteria for this hazard class	
<u>Target organs</u> Information not available	
Route of exposure	
Information not available	
STOT - REPEATED EXPOSURE	
Does not meet the classification criteria for this hazard class	
Target organs	
Information not available	
Route of exposure	
Information not available	
ASPIRATION HAZARD	
Does not meet the classification criteria for this hazard class	

11.2. Information on other hazards

Based on the available data, the product does not contain substances listed in the main European lists of potential or suspected endocrine disruptors with human health effects under evaluation.

SECTION 12. Ecological information

This product is dangerous for the environment and the aquatic organisms. In the long term, it have negative effects on aquatic environment.

12.1. Toxicity

SODIUM HYDROXIDE LC50 - for Fish EC50 - for Crustacea

< 180 mg/l/96h Gambusia affinis 40,4 mg/l/48h Ceriodaphnia sp.



Revision date

27.07.2022

Material Safetv Data Sheet

la J	alely Do	え	Board Date 05/2010	
Conforms	to Reg. (EU) 8	Board Rev. 1		
Rev. N°	Edited by	Approved by	Filed by	Page
8	RLAB	DG	RLAB	9 di 13

Board Code S-P4/2-2

N,N-dimethyltetradecylamine N-oxide	
LC50 - for Fish	10,3 mg/l/96h
EC50 - for Crustacea	2,46 mg/l/48h
EC50 - for Algae / Aquatic Plants	0,66 mg/l/72h
Chronic NOEC for Fish	0,495 mg/l 15 day
Chronic NOEC for Crustacea	0,7 mg/l
Chronic NOEC for Algae / Aquatic Plants	0,25 mg/l
SODIUM HYPOCHLORITE, SOLUTION 2,2% CI ACTIVE	
LC50 - for Fish	0,059 mg/l/96h Oncorhynchus mykiss
EC50 - for Crustacea	0,04 mg/l/48h Daphnia magna
EC50 - for Algae / Aquatic Plants	46 mg/l/72h Gracilaria tenuistipitata
12.2. Persistence and degradability	
SODIUM HYDROXIDE	
Degradability: information not available	
SODIUM HYPOCHLORITE, SOLUTION	
2,2% CI ACTIVE Solubility in water	1000 - 10000 mg/l
Degradability: information not available	1000 - 10000 High
Degradability. Information not available	
12.3. Bioaccumulative potential	
SODIUM HYPOCHLORITE, SOLUTION	
2,2% CI ACTIVE Partition coefficient: n-octanol/water	-3,42
	-3,42
12.4. Mobility in soil	
SODIUM HYPOCHLORITE, SOLUTION	
2,2% CI ACTIVE	2,0696
Partition coefficient: soil/water	-2,9686

12.5. Results of PBT and vPvB assessment

On the basis of available data, the product does not contain any PBT or vPvB in percentage ≥ than 0,1%.

12.6. Endocrine disrupting properties

Based on the available data, the product does not contain substances listed in the main European lists of potential or suspected endocrine disruptors with environmental effects under evaluation.

12.7. Other adverse effects

Information not available

SECTION 13. Disposal considerations

13.1. Waste treatment methods

Reuse, when possible. Product residues should be considered special hazardous waste. The hazard level of waste containing this product should be evaluated according to applicable regulations.

Disposal must be performed through an authorised waste management firm, in compliance with national and local regulations.

Waste transportation may be subject to ADR restrictions.

CONTAMINATED PACKAGING

Contaminated packaging must be recovered or disposed of in compliance with national waste management regulations.

NEW FADOR	
Document n°	
66/09	

Material Safety Data Sheet Conforms to Reg. (EU) 878/2020

NEW FADOR	R Conforms to Reg. (EU) 878/2020					Board Rev. 1
Document n°	Revision date	Rev. N°	Edited by	Approved by	Filed by	Page
66/09	27.07.2022	8	RLAB	DG	RLAB	10 di 13

14.1. UN number or ID number

ADR / RID, IMDG, 1791 IATA:

14.2. UN proper shipping name

ADR / RID:	HYPOCHLORITE SOLUTION
IMDG:	HYPOCHLORITE SOLUTION
IATA:	HYPOCHLORITE SOLUTION

14.3. Transport hazard class(es)

ADR / RID:	Class: 8	Label: 8
IMDG:	Class: 8	Label: 8
IATA:	Class: 8	Label: 8

Ш

14.4. Packing group

ADR / RID, IMDG, IATA:

14.5. Environmental hazards

ADR / RID:	Environmentally Hazardous	
IMDG:	Marine Pollutant	

IATA: NO

For Air transport, environmentally hazardous mark is only mandatory for UN 3077 and UN 3082.

14.6. Special precautions for user

ADR / RID:	HIN - Kemler: 80	Limited Quantities: 5 L	Tunnel restriction code: (E)
	Special provision: 521		
IMDG:	EMS: F-A, S-B	Limited Quantities: 5 L	
IATA:	Cargo:	Maximum quantity: 60 L	Packaging instructions: 856
	Pass.:	Maximum quantity: 5 L	Packaging instructions: 852
	Special provision:	A3, A803	•••

14.7. Maritime transport in bulk according to IMO instruments

Information not relevant

SECTION 15. Regulatory information

15.1. Safety, health and environmental regulations/legislation specific for the substance or mixture



Board Code S-P4/2-2

Board Date 05/2010

NEW FADOR	Material Safety Data Sheet				Board Code S-P4/2-2 Board Date 05/2010 Board Rev. 1	
Document n°	Revision date	Page				
66/09	27.07.2022	8	RLAB	DG	RLAB	11 di 13

Restrictions relating to the product or contained substances pursuant to Annex XVII to EC Regulation 1907/2006

Product Point	:	3
Contained substance		

Point

Regulation (EU) 2019/1148 - on the marketing and use of explosives precursors not applicable

75

Substances in Candidate List (Art. 59 REACH) On the basis of available data, the product does not contain any SVHC in percentage \geq than 0,1%.

Substances subject to authorisation (Annex XIV REACH) None

Substances subject to exportation reporting pursuant to Regulation (EU) 649/2012: None

Substances subject to the Rotterdam Convention: None

Substances subject to the Stockholm Convention: None

Healthcare controls

Workers exposed to this chemical agent must not undergo health checks, provided that available risk-assessment data prove that the risks related to the workers' health and safety are modest and that the 98/24/EC directive is respected.

Regulation (EC) No. 648/2004 Ingredients according to Regulation (EC) No. 648/2004

The surfactant(s) contained in this preparation complies(comply) with the biodegradability criteria as laid down in Regulation (EC) No. 648/2004 on detergents. Data to support this assertion are held at the disposal of the competent authorities of the Member States and will be made available to them, at their direct request or at the request of a detergent manufacturer.

German regulation on the classification of substances hazardous to water (AwSV, vom 18. April 2017) WGK 2: Hazard to waters

15.2. Chemical safety assessment

A chemical safety assessment has not been performed for the preparation/for the substances indicated in section 3.

SECTION 16. Other information

Text of hazard (H) indications mentioned in section 2-3 of the sheet:

Met. Corr. 1	Substance or mixture corrosive to metals, category 1
Acute Tox. 4	Acute toxicity, category 4
Skin Corr. 1A	Skin corrosion, category 1A
Eye Dam. 1	Serious eye damage, category 1
STOT SE 3	Specific target organ toxicity - single exposure, category 3
Aquatic Acute 1	Hazardous to the aquatic environment, acute toxicity, category 1
Aquatic Chronic 1	Hazardous to the aquatic environment, chronic toxicity, category 1
Aquatic Chronic 3	Hazardous to the aquatic environment, chronic toxicity, category 3
H290	May be corrosive to metals.
H302	Harmful if swallowed.
H314	Causes severe skin burns and eye damage.
H318	Causes serious eye damage.
H335	May cause respiratory irritation.
H400	Very toxic to aquatic life.

Material Safety Data Sheet

Conforms to Reg. (EU) 878/2020

2	12 di 13
	Page
	Board Rev. 1
	Board Date 05/2010
	Board Code S-P4/2-2

Document n°	Revision date	Rev. N°	Edited by	Approved by	Filed by	Page
66/09	27.07.2022	8	RLAB	DG	RLAB	12 di 13

H410	Very toxic to aquatic life with long lasting effects.
H412	Harmful to aquatic life with long lasting effects.
EUH031	Contact with acids liberates toxic gas.
EUH206	Warning! Do not use together with other products. May release dangerous gases (chlorine).

LEGEND:

- ADR: European Agreement concerning the carriage of Dangerous goods by Road
- ATE: Acute Toxicity Estimate
- CAS: Chemical Abstract Service Number
- CE50: Effective concentration (required to induce a 50% effect)
- CE: Identifier in ESIS (European archive of existing substances)
- CLP: Regulation (EC) 1272/2008
- DNEL: Derived No Effect Level
- EmS: Emergency Schedule
- GHS: Globally Harmonized System of classification and labeling of chemicals
- IATA DGR: International Air Transport Association Dangerous Goods Regulation
- IC50: Immobilization Concentration 50%
- IMDG: International Maritime Code for dangerous goods
- IMO: International Maritime Organization
- INDEX: Identifier in Annex VI of CLP
- LC50: Lethal Concentration 50%
- LD50: Lethal dose 50%
- OEL: Occupational Exposure Level
- PBT: Persistent bioaccumulative and toxic as REACH Regulation
- PEC: Predicted environmental Concentration
- PEL: Predicted exposure level
- PNEC: Predicted no effect concentration
- REACH: Regulation (EC) 1907/2006
- RID: Regulation concerning the international transport of dangerous goods by train
- TLV: Threshold Limit Value
- TLV CEILING: Concentration that should not be exceeded during any time of occupational exposure.
- TWA: Time-weighted average exposure limit
- TWA STEL: Short-term exposure limit
- VOC: Volatile organic Compounds
- vPvB: Very Persistent and very Bioaccumulative as for REACH Regulation
- WGK: Water hazard classes (German).

GENERAL BIBLIOGRAPHY

- 1. Regulation (EC) 1907/2006 (REACH) of the European Parliament 2. Regulation (EC) 1272/2008 (CLP) of the European Parliament
- 3. Regulation (EU) 2020/878 (II Annex of REACH Regulation)

- Regulation (EC) 790/2009 (I Atp. CLP) of the European Parliament
 Regulation (EU) 286/2011 (II Atp. CLP) of the European Parliament
 Regulation (EU) 618/2012 (III Atp. CLP) of the European Parliament
- 7. Regulation (EU) 487/2013 (IV Atp. CLP) of the European Parliament 8. Regulation (EU) 944/2013 (V Atp. CLP) of the European Parliament
- 9. Regulation (EU) 605/2014 (VI Atp. CLP) of the European Parliament
- 10. Regulation (EU) 2015/1221 (VII Atp. CLP) of the European Parliament
- 11. Regulation (EU) 2016/918 (VIII Atp. CLP) of the European Parliament
- 12. Regulation (EU) 2016/1179 (IX Atp. CLP)
- 13. Regulation (EU) 2017/776 (X Atp. CLP)
- 14. Regulation (EU) 2018/669 (XI Atp. CLP)
- 15. Regulation (EU) 2019/521 (XII Atp. CLP)
- 16. Delegated Regulation (UE) 2018/1480 (XIII Atp. CLP)
- 17. Regulation (EU) 2019/1148
- Delegated Regulation (UE) 2020/217 (XIV Atp. CLP)
 Delegated Regulation (UE) 2020/1182 (XV Atp. CLP)
- 20. Delegated Regulation (UE) 2021/643 (XVI Atp. CLP)
- 21. Delegated Regulation (UE) 2021/849 (XVII Atp. CLP)
- The Merck Index. 10th Edition
- Handling Chemical Safety
- INRS Fiche Toxicologique (toxicological sheet)
- Patty Industrial Hygiene and Toxicology
- N.I. Sax Dangerous properties of Industrial Materials-7, 1989 Edition
- IFA GESTIS website
- ECHA website

- Database of SDS models for chemicals - Ministry of Health and ISS (Istituto Superiore di Sanità) - Italy

Note for users:

The information contained in the present sheet are based on our own knowledge on the date of the last version. Users must verify the suitability and thoroughness of provided information according to each specific use of the product.

NEW FADOR	Material Safety Data Sheet					Board Code S-P4/2-2 Board Date 05/2010 Board Rev. 1
Document n°	Revision date	Page				
66/09	27.07.2022	8	RLAB	DG	RLAB	13 di 13

This document must not be regarded as a guarantee on any specific product property.

The use of this product is not subject to our direct control; therefore, users must, under their own responsibility, comply with the current health and safety laws and regulations. The producer is relieved from any liability arising from improper uses.

Provide appointed staff with adequate training on how to use chemical products.

CALCULATION METHODS FOR CLASSIFICATION

Chemical and physical hazards: Product classification derives from criteria established by the CLP Regulation, Annex I, Part 2. The data for evaluation of chemical-physical properties are reported in section 9.

Health hazards: Product classification is based on calculation methods as per Annex I of CLP, Part 3, unless determined otherwise in Section 11. Environmental hazards: Product classification is based on calculation methods as per Annex I of CLP, Part 4, unless determined otherwise in Section 12.

Changes to previous review:

The following sections were modified: 01 / 02 / 03 / 08 / 09 / 11 / 12 / 14 / 15 / 16.